

Sol-Ark 8K-P Spec Sheet



Solar I	nput Power 9000W
Max Allowed PV Power	5500W + 5500W = 11000W
Max PV Power Delivered to Battery & AC Outputs	8000W
Max DC Voltage (Voc)	500V @ 18A, 450V @ 20A
MPPT Voltage Range	150-425V
Starting Voltage	125V
Number of MPPT	2
Max Solar Strings Per MPPT	2
Max DC Current per MPPT (Self Limiting)	20A
Max AC Coupled Input (Micro/String Inverters)	9600W

AC Output Power 8kW	On-Grid & Off-Grid				
Connections	120/240/208V Split Phase				
Continuous AC Power to Grid (On-Grid)	8000W 33.3A-L (240V)				
Continuous AC Power to Load (Off- Grid)	8000W 33.3A-L (240V)				
Surge AC Power 10sec	16,000VA L-L (240V)				
Parallel Stacking	No				
Frequency	60/50Hz				
Continuous AC Power with Grid or	15120W 63A L-L (240V)				
Generator	7560W 63A L-N (120V)				
CEC Efficiency	96.5% (Peak 97.5%)				
Idle Consumption Typical—No Load	60W				
Sell Back Power Modes	Limited to Household/Fully Grid-Tied				
Design (DC to AC)	Transformerless DC				
Response Time (Grid-Tied to Off-Grid)	4ms				
Power Factor	+/- 0.9 - 1.0				

Battery (optional) Output Power 8000W				
Туре	Lead-Acid or Li-Ion			
Nominal DC Input	48V			
Capacity	50 — 9900Ah			
Voltage Range	43.0 — 63.0V			
Continuous Battery Charging Output	185A			
Charging Curve	3-Stage w/ Equalization			
Grid to Batt Charging Efficiency	96.0%			
External Temperature Sensor	Included			
Current Shunt for Accurate % SOC	Integrated			
External Gen Start Based on Voltage or %SOC	Integrated			
Communication to Lithium Battery	CanBus & RS485			

General	
Dimensions (H x W x D)	30.0" x 18.3" x 10.0"
Weight	78 lbs
Enclosure	NEMA 3R
Ambient Temperature	-25-55°C, >45°C Derating
Installation Style	Wall-Mounted
Wi-Fi & LAN Communication	Included
Standard Warranty (verified by HALT Testing)	5 Years

Protections & Certifications	
Electronics Certified Safety by SGS Labs to NEC & UL Specs - NEC 690.4B & NEC 705.4/6	Yes
Grid Sell Back — UL1741-2010/2018, IEE- E1547a-2003/2014, FCC 15 Class B, UL1741SA, CA Rule 21, HECO Rule 14H	Yes
PV DC Disconnect Switch — NEC 240.15	Integrated
Ground Fault Detection — NEC 690.5	Integrated
PV Rapid Shutdown Control — NEC 690.12	Integrated
PV Arc Fault Detection — NEC 690.11	Integrated
PV Input Lightning Protection	Integrated
PV String Input Reverse Polarity Protection	Integrated
AC Output Breakers - 63A	Integrated
250A Battery Breaker / Disconnect	Integrated
Surge Protection	DC Type II / AC Type II

Design Type	DC Transformerless				AC Coupled			
565.8, p.				Generac	SolarEdge	Panasonic	Enphase	Tesla 2x
	Sol-Ark 12K	Sol-Ark 8K	Sal-Ark 5K	PWRcell 7.6	Energy Hub	(Darfon)	2x10	Powerwall2 +
Brand & Model	JOI AIR 12R	JOI AIR OR	JOI-AIR JR	+4xS2500	7.6 32xP400	2xH5001	+36xIQ7P	String Inv
MSRP Price	\$6,900	\$6,100	\$4,500	\$6,500	\$7,600	\$6,200	\$28,700	\$19,400
Solar PV Continuous Power	12KW	9KW	6.5KW	11KW	7.6KW	2x6KW	10.4KW	12KW
Inverter AC Continuous Power	9KW	8KW	5KW	7.6KW	7.6KW	2x5KW	10.4KW	2x5KW
Inverter Battery Continuous Power	9KW	8KW	5KW	9KW	6.1KW	2x5.5KW	2x3.8KW	2x5KW
Off Grid Inverter AC Peak Power (5s)	16KW	16KW	16KW	12KW	6.9KW	13KW	8.8KW	14KW
System Idle Power	60W	60W	60W	221100	0.0.0.0	200W		78W
AC to DC Charger	185A	185A	120A	6.7KW	5KW?	120A	N/A	N/A
ne to be charge.	color	color	color	017100	J. C.	220/1	.40	14/1
User Interface	touch	touch	touch	Text	Text	Text	Х	x
PV to Batt Efficiency @ 65%	97.5%	97.5%	97.5%	92.0%	92.5%	91.0%	92.0%	92.5%
AC to Batt Efficiency @ 65%	96.0%	96.0%	96.0%	93.0%	93.5%	90.0%	95.0%	95.0%
Batt to AC Efficiency @ 65%	95.5%	95.5%	95.5%	93.0%	93.5%	90.0%	95.0%	95.0%
Batt to Ac Efficiency @ 65%	33.370	93.370	93.370	33.0%	73/3/0	30.070	33.0%	33.0%
On Grid PV to AC Efficiency @ CEC	96.5%	96.5%	96.5%	95.5%	98.0%	95.5%	97.0%	97.0%
Time of Use or Off Grid	70/	70/	70/	150/	1/10/	100/	120/	120/
PV -> Batt -> AC <i>Losses</i> @ 65%	7 %	7%	7%	15%	14%	19%	13%	13%
Grid Failure UPS Transfer Time	4ms	4ms	4ms	1000ms	3000ms	20ms	2000ms	2000ms
Low Cost Easy Install	✓	✓	_ ✓	√	✓	✓	√	✓
Warranty	10 yr	5/10 yr	5 yr	10 yr	12/20/25 yr	10 yr	10 yr	10 yr
AC Coupling to existing Inverters	✓	✓	✓	Х	✓	✓	✓	✓
Parallel Stacking	✓	×	X	X	✓	✓	✓	✓
120/240/208V 3Phase	✓	Х	X	✓	Х	Х	Х	✓
Generator Charging	√	✓	✓	Χ	Х	Х	Х	Х
AC Load Shedding for TOU & Off Grid	✓	✓	✓	✓	Х	Х	Х	Х
California & HECO (Grid Sell)	✓	✓	Х	✓	✓	✓	✓	✓
NEC UL1699B Arc Fault	✓	✓	✓	✓	✓	X	✓	✓
Outdoor Enclosure	✓	✓	✓	√	✓	Х	✓	✓
	20KWh	20KWh	20KWh	18KWh 3500c	2x9.8KWh	18KWh	21.0KWh	28KWh
Battery Bank	6000cycles +\$13K	+\$13K	+\$13K	+\$13K	3000c +\$12K	3000c +\$15K	6000cycles	3500cycles